

**BLUE HILL HARBOR  
MAINE  
NAVIGATION IMPROVEMENT PROJECT**

**APPENDIX D  
COST ENGINEERING**

*This Page Intentionally Left Blank*

## **COST ESTIMATE**

The cost estimate is based on dredge quantities developed by the Civil Engineering Section. The Recommended Plan includes constructing a new 80-ft wide, 6-ft deep channel along with a new turning basin. There is no pre-existing federal navigation project in this area.

Environmental testing in the harbor indicates that the top 2-ft of sediment are contaminated with PAHs; thus, the Recommended Plan also includes construction of a new CAD cell to place and cap this material.

Numerous alternatives were considered for this project, including different channel depths (5-ft and 7-ft), as well as overland disposal for the contaminated material. The Recommended Plan was selected through an economic analysis.

### **Assumptions**

- Construction methodology for clean material: the CEDEP estimate assumes that mechanical dredging equipment will be used throughout the project. The estimate assumes an 8-cy bucket will place clean material directly into two 1,500-cy bottom dump scows which will be towed 14-miles to the Eastern Passage Disposal Site (EPDS) and disposed of. Some of the clean material is to be used as a cap for the CAD cell, and will therefore only be hauled for ¼-mile. The estimate assumes one 3000 HP tug will haul the scows to/from the dredge site and the disposal areas.
- Construction methodology for contaminated material: the CEDEP estimate assumes that mechanical dredging equipment will be used throughout the project. The estimate assumes an 8-cy bucket will place contaminated material directly into a 1,500-cy bottom dump scow which will be towed ¼-mile to the CAD cell and disposed of. The estimate assumes one 3000 HP tug will haul the scows to/from the dredge site and the CAD cell area. It should be noted that, due to the substantial tide changes at this site, it's assumed that there will be a "dedicated" scow for storing the contaminated material. That way, the contractor will be able to continue excavating both material types, even if he can't access the CAD cell area due to the tides.
- Estimate assumes the prime contractor will self-perform all work.
- Estimate assumes that the prime contractor will mobilize from Maine, based on historic information of available contractors in the area.
- Estimate assumes that contractor will pay Davis Bacon wage rates for Hancock County in Maine. If the winning contractor ends up coming from outside of Maine, this could cause a rise in costs due to potentially higher wage rates.
- Estimate assumes open competition and invitation for bid procurement method.

## **RISK ANALYSIS**

Risk Mitigation was conducted through an Abbreviated Risk Analysis (ARA) of the project as it is currently presented in addition to the acknowledgement of risk in the scope and estimated quantities. The District has mitigated this risk through a conservative approach to the excavation and hauling of dredge material as well as utilizing a conservative cost of fuel. The values included in the project cost provide an amount that the PDT is confident will provide substantive costs to mitigate any issues. The District will continue to monitor and include all risks in continuing assessment of contingency and amend as necessary as an essential element to the continued development of the project. The potential risk areas identified through formal risk and sensitivity analysis were mobilization & demobilization, dredge & disposal of clean material to the EPDS and dredge & disposal of contaminated material to the CAD cell.

The ARA was developed relying on local District staff to provide expertise and information gathering. The cost engineer facilitated a risk assessment meeting with the PDT in addition to a qualitative analysis to produce a risk register that served as the framework for the risk analysis.

The ARA assumes the Project Development Stage/Alternative is "Feasibility (Recommended Plan)" with a "Low Risk" risk category based on the experience of the cost engineer and vetted with the PDT. The resultant contingencies are 15.04% for the Total Construction Estimate, 13.62% for Total Planning, Engineering & Design, and 16.83% for Total Construction Management. These contingency percentages were then utilized in the Total Project Cost Summary.

There is no one significant risk factor for this project that stands above the rest. The risks associated with the project are typical for improvement dredging and are derived from the district's standard practices for developing quantities, acquisition strategy, and cost estimate assumptions regarding what equipment will be utilized to construct the project.

## **TOTAL PROJECT COST SUMMARY (TPCS)**

The Total Project Cost Summary (TPCS) was then computed to summarize the construction cost, project first cost, and the Total Project Cost or the Fully Funded Cost. The TPCS was utilized to calculate the construction cost estimate applied contingency and escalated to the midpoints of the features of work and the remaining work breakdown structure to include Planning, Engineering & Design (PED) and Construction Management. The inputs of the TPCS, to include percentages for the PED phase and Construction Management were obtained from the project manager.

The resultant TPCS from the cost estimate, risk analysis, and escalation is \$3,138,000 with an estimated Federal cost of \$2,824,000 and Non-Federal cost of \$628,000

utilizing a 90%/10% Federal to Non-Federal cost split, plus an additional 10% of project costs to be paid to the US Treasury in accordance with Congressional mandates. Including feasibility study costs of \$352,000, the total estimated Federal cost of the project is \$3,050,000.

*This Page Intentionally Left Blank*

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

Printed:2/3/2022

Page 1 of 2

PROJECT: **Blue Hill Section 107**

PROJECT NO: **328230**

LOCATION: **Blue Hill, Maine**

DISTRICT: **New England District**

PREPARED: **5/19/2021**

UPDATED: **2/1/2022**

POC: **CHIEF, COST ENGINEERING, Jeffrey Gaeta**

This Estimate reflects the scope and schedule in report;

Blue Hill Harbor, Section 107 Navigation Improvement Study

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)					TOTAL PROJECT COST (FULLY FUNDED)				
Dispose Dredged Material in CAD Cell						Program Year (Budget EC): 2022 Effective Price Level Date: 1-Oct- 21									
WBS NUMBER	Civil Works Feature & Sub-Feature Description	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	ESC (%)	COST (\$K)	CNTG (\$K)	REMAINING COST (\$K)	Spent Thru: 1-Oct-21 (\$K)	TOTAL FIRST COST (\$K)	ESC (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
12	NAVIGATION PORTS & HARBORS - MOB	\$467	\$70	15%	\$537	11.7%	\$521	\$78	\$599		\$599	6.4%	\$554	\$83	\$637
12	NAVIGATION PORTS & HARBORS - DREDG	\$1,618	\$243	15%	\$1,861	11.7%	\$1,807	\$272	\$2,078		\$2,078	6.4%	\$1,922	\$289	\$2,211
			-	-		-						-			
CONSTRUCTION ESTIMATE TOTALS:		\$2,085	\$314		\$2,398	11.7%	\$2,328	\$350	\$2,678		\$2,678	6.4%	\$2,476	\$372	\$2,848
01	LANDS AND DAMAGES	\$9			\$9	8.4%	\$10		\$10		\$10	6.4%	\$10		\$10
30	PLANNING, ENGINEERING & DESIGN	\$304	\$41	14%	\$345	2.4%	\$311	\$42	\$354		\$354	3.6%	\$322	\$44	\$366
31	CONSTRUCTION MANAGEMENT	\$177	\$30	17%	\$207	2.4%	\$181	\$31	\$212		\$212	5.1%	\$191	\$32	\$223
PROJECT COST TOTALS:		\$2,575	\$385	15%	\$2,960		\$2,830	\$423	\$3,253		\$3,253	6.0%	\$2,999	\$448	\$3,447

CHIEF, COST ENGINEERING, Jeffrey Gaeta

PROJECT MANAGER, Mark Habel

CHIEF, REAL ESTATE, Timothy Shugert

CHIEF, PLANNING, John Kennelly

CHIEF, ENGINEERING, Dave Margolis

CHIEF, OPERATIONS, Eric Pedersen

CHIEF, CONSTRUCTION, Sean Dolan

CHIEF, CONTRACTING, Sheila Winston-Vincuilla

CHIEF, PM-PB, Janet Harrington

CHIEF, DPM, Scott Acone

**ESTIMATED TOTAL PROJECT COST: \$3,447**

ESTIMATED FEDERAL COST: **90%** \$3,103

ESTIMATED NON-FEDERAL COST: **10%** \$345

ADDITIONAL 10% NON-FEDERAL COST: \$345

**22 - FEASIBILITY STUDY (CAP studies): \$352**

ESTIMATED FEDERAL COST: 64% \$226

ESTIMATED NON-FEDERAL COST: 36% \$126

**ESTIMATED FEDERAL COST OF PROJECT \$3,329**

ESTIMATED NON-FEDERAL COST OF PROJECT \$815

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

Printed:2/3/2022

Page 2 of 2

\*\*\*\* CONTRACT COST SUMMARY \*\*\*\*

PROJECT: Blue Hill Section 107

LOCATION: Blue Hill, Maine

This Estimate reflects the scope and schedule in report;

Blue Hill Harbor, Section 107 Navigation Improvement Study

DISTRICT: New England District

POC: CHIEF, COST ENGINEERING, Jeffrey Gaeta

PREPARED: 5/19/2021

UPDATED: 2/1/2022

WBS Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)				
<b>Dispose Dredged Material in CAD Cell</b>		Estimate Prepared: <b>19-May-21</b> Estimate Price Level: 1-Oct-20				Program Year (Budget EC): 2022 Effective Price Level Date: 1-Oct-21								
		RISK BASED												
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL (\$K) F	ESC (%) G	COST (\$K) H	CNTG (\$K) I	TOTAL (\$K) J	Mid-Point Date P	ESC (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
<b>PHASE 1 or CONTRACT 1</b>														
<b>12</b>	NAVIGATION PORTS & HARBORS - MOB	\$467	\$70	15.0%	\$537	11.7%	\$521	\$78	\$599	2024Q1	6.4%	\$554	\$83	\$637
<b>12</b>	NAVIGATION PORTS & HARBORS - DREDG	\$1,618	\$243	15.0%	\$1,861	11.7%	\$1,807	\$272	\$2,078	2024Q1	6.4%	\$1,922	\$289	\$2,211
<b>CONSTRUCTION ESTIMATE TOTALS:</b>		\$2,085	\$314	15.0%	\$2,398		\$2,328	\$350	\$2,678			\$2,476	\$372	\$2,848
<b>01</b>	LANDS AND DAMAGES	\$9			\$9	8.4%	\$10		\$10	2024Q1	6.4%	\$10		\$10
<b>30</b>	PLANNING, ENGINEERING & DESIGN													
8.6%	Project Management	\$40	\$5	13.6%	\$45	2.4%	\$41	\$6	\$47	2023Q2	3.1%	\$42	\$6	\$48
4.3%	Planning & Environmental Compliance	\$20	\$3	13.6%	\$23	2.4%	\$20	\$3	\$23	2023Q2	3.1%	\$21	\$3	\$24
30.6%	Engineering & Design	\$143	\$19	13.6%	\$162	2.4%	\$146	\$20	\$166	2023Q2	3.1%	\$151	\$21	\$172
5.4%	Reviews, ATRs, IEPRs, VE	\$25	\$3	13.6%	\$28	2.4%	\$26	\$3	\$29	2023Q2	3.1%	\$26	\$4	\$30
	Life Cycle Updates (cost, schedule, risks)			13.6%										
4.3%	Contracting & Reprographics	\$20	\$3	13.6%	\$23	2.4%	\$20	\$3	\$23	2024Q1	5.1%	\$22	\$3	\$24
1.3%	Engineering During Construction	\$6	\$1	13.6%	\$7	2.4%	\$6	\$1	\$7	2024Q1	5.1%	\$6	\$1	\$7
6.4%	Planning During Construction	\$30	\$4	13.6%	\$34	2.4%	\$31	\$4	\$35	2023Q2	3.1%	\$32	\$4	\$36
	Adaptive Management & Monitoring			13.6%										
4.3%	Project Operations	\$20	\$3	13.6%	\$23	2.4%	\$20	\$3	\$23	2025Q1	7.7%	\$22	\$3	\$25
<b>31</b>	CONSTRUCTION MANAGEMENT													
6.0%	Construction Management	\$125	\$21	16.8%	\$146	2.4%	\$128	\$22	\$150	2024Q1	5.1%	\$135	\$23	\$157
2.0%	Project Operation:			16.8%										
2.5%	Project Management	\$52	\$9	16.8%	\$61	2.4%	\$53	\$9	\$62	2024Q1	5.1%	\$56	\$9	\$65
<b>CONTRACT COST TOTALS:</b>		\$2,575	\$385		\$2,960		\$2,830	\$423	\$3,253			\$2,999	\$448	\$3,447

D-5b



# **WALLA WALLA COST ENGINEERING MANDATORY CENTER OF EXPERTISE**

## **COST AGENCY TECHNICAL REVIEW CERTIFICATION STATEMENT**

For Project No. 32830

### **NAE – Blue Hill Harbor Section 107 Navigation Improvement Project**

The Blue Hill Harbor Section 107 – Navigation Improvement Project as presented by New England District, has undergone a successful Cost Agency Technical Review (Cost ATR), performed by the Walla Walla District Cost Engineering Mandatory Center of Expertise (Cost MCX) team. The Cost ATR included study of the project scope, report, cost estimates, schedules, escalation, and risk-based contingencies. This certification signifies the products meet the quality standards as prescribed in ER 1110-2-1150 Engineering and Design for Civil Works Projects and ER 1110-2-1302 Civil Works Cost Engineering.

As of June 25, 2021, the Cost MCX certifies the estimated total project cost:

FY21 Project First Cost:	\$2,960,000
Fully Funded Total Project Cost:	\$3,138,000
Federal Cost of Project:	\$3,050,000

It remains the responsibility of the District to correctly reflect these cost values within the Final Report and to implement effective project management controls and implementation procedures including risk management through the period of Federal participation.



2021.06.25 08:51:41  
-07'00'

**Michael P. Jacobs, PE, CCE**  
**Chief, Cost Engineering MCX**  
**Walla Walla District**

**\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\***

Printed:6/25/2021  
Page 1 of 2

PROJECT: **Blue Hill Section 107**  
PROJECT NO: **328230**  
LOCATION: **Blue Hill, Maine**

DISTRICT: **New England District**

PREPARED: **5/19/2021**

POC: **CHIEF, COST ENGINEERING, Jeffrey Gaeta**

This Estimate reflects the scope and schedule in report; Blue Hill Harbor, Section 107 Navigation Improvement Study

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)					TOTAL PROJECT COST (FULLY FUNDED)				
Dispose Dredged Material in CAD Cell						Program Year (Budget EC): 2021 Effective Price Level Date: 1-Oct- 20 Spent Thru: 1-Oct-20									
WBS NUMBER	Civil Works Feature & Sub-Feature Description	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	ESC (%)	COST (\$K)	CNTG (\$K)	REMAINING COST (\$K)		TOTAL FIRST COST (\$K)	ESC (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
12	NAVIGATION PORTS & HARBORS	\$2,085	\$314	15%	\$2,398		\$2,085	\$314	\$2,398		\$2,398	6.0%	\$2,209	\$332	\$2,541
				-		-						-			
				-		-						-			
				-		-						-			
CONSTRUCTION ESTIMATE TOTALS:		\$2,085	\$314		\$2,398		\$2,085	\$314	\$2,398		\$2,398	6.0%	\$2,209	\$332	\$2,541
01	LANDS AND DAMAGES	\$9			\$9		\$9		\$9		\$9	6.0%	\$10		\$10
30	PLANNING, ENGINEERING & DESIGN	\$304	\$41	14%	\$345		\$304	\$41	\$345		\$345	5.4%	\$320	\$44	\$364
31	CONSTRUCTION MANAGEMENT	\$177	\$30	17%	\$207		\$177	\$30	\$207		\$207	7.9%	\$191	\$32	\$223
PROJECT COST TOTALS:		\$2,575	\$385	15%	\$2,960		\$2,575	\$385	\$2,960		\$2,960	6.0%	\$2,730	\$408	\$3,138

D-6

\_\_\_\_\_  
CHIEF, COST ENGINEERING, Jeffrey Gaeta

\_\_\_\_\_  
PROJECT MANAGER, Mark Habel

\_\_\_\_\_  
CHIEF, REAL ESTATE, Timothy Shugert

\_\_\_\_\_  
CHIEF, PLANNING, John Kennelly

\_\_\_\_\_  
CHIEF, ENGINEERING, Dave Margolis

\_\_\_\_\_  
CHIEF, OPERATIONS, Eric Pedersen

\_\_\_\_\_  
CHIEF, CONSTRUCTION, Sean Dolan

\_\_\_\_\_  
CHIEF, CONTRACTING, Sheila Winston-Vincuilla

\_\_\_\_\_  
CHIEF, PM-PB, Janet Harrington

\_\_\_\_\_  
CHIEF, DPM, Scott Accone

**ESTIMATED TOTAL PROJECT COST: \$3,138**  
ESTIMATED FEDERAL COST: **90%** \$2,824  
ESTIMATED NON-FEDERAL COST: **10%** \$314  
ADDITIONAL 10% NON-FEDERAL COST: \$314

**22 - FEASIBILITY STUDY (CAP studies): \$352**  
ESTIMATED FEDERAL COST: 64% **\$226**  
ESTIMATED NON-FEDERAL COST: 36% **\$126**

**ESTIMATED FEDERAL COST OF PROJECT \$3,050**  
ESTIMATED NON-FEDERAL COST OF PROJECT \$754

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

Printed:6/25/2021  
Page 2 of 2

\*\*\*\* CONTRACT COST SUMMARY \*\*\*\*

PROJECT: Blue Hill Section 107  
LOCATION: Blue Hill, Maine  
This Estimate reflects the scope and schedule in report; Blue Hill Harbor, Section 107 Navigation Improvement Study

DISTRICT: New England District  
POC: CHIEF, COST ENGINEERING, Jeffrey Gaeta

PREPARED: 5/19/2021

WBS Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)				
<b>Dispose Dredged Material in CAD Cell</b>		Estimate Prepared: <b>19-May-21</b> Estimate Price Level: 1-Oct-20				Program Year (Budget EC): 2021 Effective Price Level Date: 1-Oct-20								
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL (\$K) F	ESC (%) G	COST (\$K) H	CNTG (\$K) I	TOTAL (\$K) J	Mid-Point Date P	ESC (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
<b>PHASE 1 or CONTRACT 1</b>														
<b>12</b>	NAVIGATION PORTS & HARBORS	\$2,085	\$314	15.0%	\$2,398		\$2,085	\$314	\$2,398	2023Q1	6.0%	\$2,209	\$332	\$2,541
<b>CONSTRUCTION ESTIMATE TOTALS:</b>		\$2,085	\$314	15.0%	\$2,398		\$2,085	\$314	\$2,398			\$2,209	\$332	\$2,541
<b>01</b>	LANDS AND DAMAGES	\$9			\$9		\$9		\$9	2023Q1	6.0%	\$10		\$10
<b>30</b>	PLANNING, ENGINEERING & DESIGN													
1.9%	Project Management	\$40	\$5	13.6%	\$45		\$40	\$5	\$45	2022Q2	5.0%	\$42	\$6	\$48
1.0%	Planning & Environmental Compliance	\$20	\$3	13.6%	\$23		\$20	\$3	\$23	2022Q2	5.0%	\$21	\$3	\$24
6.9%	Engineering & Design	\$143	\$19	13.6%	\$162		\$143	\$19	\$162	2022Q2	5.0%	\$150	\$20	\$171
1.2%	Reviews, ATRs, IEPs, VE	\$25	\$3	13.6%	\$28		\$25	\$3	\$28	2022Q2	5.0%	\$26	\$4	\$30
	Life Cycle Updates (cost, schedule, risks)			13.6%										
1.0%	Contracting & Reprographics	\$20	\$3	13.6%	\$23		\$20	\$3	\$23	2023Q1	7.9%	\$22	\$3	\$25
0.3%	Engineering During Construction	\$6	\$1	13.6%	\$7		\$6	\$1	\$7	2023Q1	7.9%	\$6	\$1	\$7
1.4%	Planning During Construction	\$30	\$4	13.6%	\$34		\$30	\$4	\$34	2022Q2	5.0%	\$31	\$4	\$36
	Adaptive Management & Monitoring			13.6%										
1.0%	Project Operations	\$20	\$3	13.6%	\$23		\$20	\$3	\$23	2023Q1	7.9%	\$22	\$3	\$25
<b>31</b>	CONSTRUCTION MANAGEMENT													
6.0%	Construction Management	\$125	\$21	16.8%	\$146		\$125	\$21	\$146	2023Q1	7.9%	\$135	\$23	\$158
2.0%	Project Operation:			16.8%										
2.5%	Project Management	\$52	\$9	16.8%	\$61		\$52	\$9	\$61	2023Q1	7.9%	\$56	\$9	\$66
<b>CONTRACT COST TOTALS:</b>		\$2,575	\$385		\$2,960		\$2,575	\$385	\$2,960			\$2,730	\$408	\$3,138

*This Page Intentionally Left Blank*

ID	Task Mode	Task Name	Duration	Start	Finish	Aug '22					Sep '22					Oct '22				Nov '22				Dec '22		
						31	7	14	21	28	4	11	18	25		2	9	16	23	30	6	13	20	27	4	11
1		<b>Recommended Plan: Place Material in CAD Cell</b>																								
2																										
3		<b>PED Phase</b>	<b>365 days</b>	<b>Fri 10/1/21</b>	<b>Sat 10/1/22</b>																					
4		Develop, Solicit, & Award Construction Contract	365 days	Fri 10/1/21	Sat 10/1/22																					
5		<b>Construction Phase</b>	<b>78 days</b>	<b>Sat 10/1/22</b>	<b>Sun 12/18/22</b>																					
6		<b>Pre-Construction Activities</b>	<b>30 days</b>	<b>Sat 10/1/22</b>	<b>Mon 10/31/22</b>																					
7		Pre-Con Submittals	30 days	Sat 10/1/22	Mon 10/31/22																					
8		<b>Mobilization</b>	<b>10 days</b>	<b>Mon 10/31/22</b>	<b>Thu 11/10/22</b>																					
9		Prepare for Mobilization	5 days	Mon 10/31/22	Sat 11/5/22																					
10		Mobilize to Site	5 days	Sat 11/5/22	Thu 11/10/22																					
11		<b>Dredging</b>	<b>30 days</b>	<b>Thu 11/10/22</b>	<b>Sat 12/10/22</b>																					
12		Dredge Clean Mat'l - Haul to EPDS	12 days	Thu 11/10/22	Tue 11/22/22																					
13		Dredge CAD Cell - Haul to EPDS	5 days	Tue 11/22/22	Sun 11/27/22																					
14		Dredge Contam Mat'l - Haul to CAD Cell	11 days	Sun 11/27/22	Thu 12/8/22																					
15		Place CAD Cell Cap	2 days	Thu 12/8/22	Sat 12/10/22																					
16		<b>Demobilization</b>	<b>8 days</b>	<b>Sat 12/10/22</b>	<b>Sun 12/18/22</b>																					
17		Demobilize	5 days	Sat 12/10/22	Thu 12/15/22																					
18		Prepare Dredge for Storage	3 days	Thu 12/15/22	Sun 12/18/22																					

D-9

Project: msproj11  
Date: Mon 5/31/21

Task

Split

Milestone

Summary

Project Summary

External Tasks

External Milestone

Inactive Task

Inactive Milestone

Inactive Summary

Manual Task

Duration-only

Manual Summary Rollup

Manual Summary

Start-only

Finish-only

Deadline

Progress

Manual Progress

Page 1

**\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\***

Printed:6/3/2021

Page 1 of 4

PROJECT: **Blue Hill Section 107**

PROJECT NO: **328230**

LOCATION: **Blue Hill, Maine**

DISTRICT: **New England District**

PREPARED: **5/19/2021**

POC: **CHIEF, COST ENGINEERING, Jeffrey Gaeta**

This Estimate reflects the scope and schedule in report;

Blue Hill Harbor, Section 107 Navigation Improvement Study

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)					TOTAL PROJECT COST (FULLY FUNDED)					
Dispose Dredged Material in CAD Cell						Program Year (Budget EC): 2021 Effective Price Level Date: 1-Oct- 20 Spent Thru: 1-Oct-20					TOTAL FIRST COST					
WBS NUMBER	Civil Works Feature & Sub-Feature Description	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	ESC (%)	COST (\$K)	CNTG (\$K)	REMAINING COST (\$K)			ESC (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)	
D-10	12	NAVIGATION PORTS & HARBORS	\$2,085	\$314	15%	\$2,398		\$2,085	\$314	\$2,398		\$2,398	6.0%	\$2,209	\$332	\$2,541
				-		-						-				
				-		-						-				
				-		-						-				
	CONSTRUCTION ESTIMATE TOTALS:		\$2,085	\$314		\$2,398		\$2,085	\$314	\$2,398		\$2,398	6.0%	\$2,209	\$332	\$2,541
	01	LANDS AND DAMAGES	\$9		\$9		\$9		\$9		\$9	6.0%	\$10		\$10	
	30	PLANNING, ENGINEERING & DESIGN	\$304	\$41	14%	\$345		\$304	\$41	\$345		\$345	5.4%	\$320	\$44	\$364
	31	CONSTRUCTION MANAGEMENT	\$177	\$30	17%	\$207		\$177	\$30	\$207		\$207	7.9%	\$191	\$32	\$223
PROJECT COST TOTALS:		\$2,575	\$385	15%	\$2,960		\$2,575	\$385	\$2,960		\$2,960	6.0%	\$2,730	\$408	\$3,138	

D-10

\_\_\_\_ CHIEF, COST ENGINEERING, Jeffrey Gaeta

\_\_\_\_ PROJECT MANAGER, Mark Habel

\_\_\_\_ CHIEF, REAL ESTATE, Timothy Shugert

\_\_\_\_ CHIEF, PLANNING, John Kennelly

\_\_\_\_ CHIEF, ENGINEERING, Dave Margolis

\_\_\_\_ CHIEF, OPERATIONS, Eric Pedersen

\_\_\_\_ CHIEF, CONSTRUCTION, Sean Dolan

\_\_\_\_ CHIEF, CONTRACTING, Sheila Winston-Vincuilla

\_\_\_\_ CHIEF, PM-PB, Janet Harrington

\_\_\_\_ CHIEF, DPM, Scott Accone

**ESTIMATED TOTAL PROJECT COST: \$3,138**

ESTIMATED FEDERAL COST: **90%** \$2,824

ESTIMATED NON-FEDERAL COST: **10%** \$314

ADDITIONAL 10% NON-FEDERAL COST: \$314

**22 - FEASIBILITY STUDY (CAP studies): \$352**

ESTIMATED FEDERAL COST: 64% **\$226**

ESTIMATED NON-FEDERAL COST: 36% **\$126**

**ESTIMATED FEDERAL COST OF PROJECT \$3,050**

ESTIMATED NON-FEDERAL COST OF PROJECT \$754

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

Printed:6/3/2021  
Page 2 of 4

\*\*\*\* CONTRACT COST SUMMARY \*\*\*\*

PROJECT: Blue Hill Section 107  
LOCATION: Blue Hill, Maine  
This Estimate reflects the scope and schedule in report; Blue Hill Harbor, Section 107 Navigation Improvement Study

DISTRICT: New England District  
POC: CHIEF, COST ENGINEERING, Jeffrey Gaeta

PREPARED: 5/19/2021

WBS Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)				
<b>Dispose Dredged Material in CAD Cell</b>		Estimate Prepared: <b>19-May-21</b> Estimate Price Level: 1-Oct-20				Program Year (Budget EC): 2021 Effective Price Level Date: 1-Oct-20								
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL (\$K) F	ESC (%) G	COST (\$K) H	CNTG (\$K) I	TOTAL (\$K) J	Mid-Point Date P	ESC (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
<b>12</b>	NAVIGATION PORTS & HARBORS	\$2,085	\$314	15.0%	\$2,398		\$2,085	\$314	\$2,398	2023Q1	6.0%	\$2,209	\$332	\$2,541
<b>CONSTRUCTION ESTIMATE TOTALS:</b>		\$2,085	\$314	15.0%	\$2,398		\$2,085	\$314	\$2,398			\$2,209	\$332	\$2,541
<b>01</b>	LANDS AND DAMAGES	\$9			\$9		\$9		\$9	2023Q1	6.0%	\$10		\$10
<b>30</b>	PLANNING, ENGINEERING & DESIGN													
1.9%	Project Management	\$40	\$5	13.6%	\$45		\$40	\$5	\$45	2022Q2	5.0%	\$42	\$6	\$48
1.0%	Planning & Environmental Compliance	\$20	\$3	13.6%	\$23		\$20	\$3	\$23	2022Q2	5.0%	\$21	\$3	\$24
6.9%	Engineering & Design	\$143	\$19	13.6%	\$162		\$143	\$19	\$162	2022Q2	5.0%	\$150	\$20	\$171
1.2%	Reviews, ATRs, IEPs, VE	\$25	\$3	13.6%	\$28		\$25	\$3	\$28	2022Q2	5.0%	\$26	\$4	\$30
	Life Cycle Updates (cost, schedule, risks)			13.6%										
1.0%	Contracting & Reprographics	\$20	\$3	13.6%	\$23		\$20	\$3	\$23	2023Q1	7.9%	\$22	\$3	\$25
0.3%	Engineering During Construction	\$6	\$1	13.6%	\$7		\$6	\$1	\$7	2023Q1	7.9%	\$6	\$1	\$7
1.4%	Planning During Construction	\$30	\$4	13.6%	\$34		\$30	\$4	\$34	2022Q2	5.0%	\$31	\$4	\$36
	Adaptive Management & Monitoring			13.6%										
1.0%	Project Operations	\$20	\$3	13.6%	\$23		\$20	\$3	\$23	2023Q1	7.9%	\$22	\$3	\$25
<b>31</b>	CONSTRUCTION MANAGEMENT													
6.0%	Construction Management	\$125	\$21	16.8%	\$146		\$125	\$21	\$146	2023Q1	7.9%	\$135	\$23	\$158
2.0%	Project Operation:			16.8%										
2.5%	Project Management	\$52	\$9	16.8%	\$61		\$52	\$9	\$61	2023Q1	7.9%	\$56	\$9	\$66
<b>CONTRACT COST TOTALS:</b>		\$2,575	\$385		\$2,960		\$2,575	\$385	\$2,960			\$2,730	\$408	\$3,138

D-11

\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

Printed:6/3/2021

Page 3 of 4

PROJECT: **Blue Hill Section 107**  
PROJECT NO: **328230**  
LOCATION: **Blue Hill, Maine**

DISTRICT: **New England District**

PREPARED: **5/19/2021**

POC: **CHIEF, COST ENGINEERING, Jeffrey Gaeta**

This Estimate reflects the scope and schedule in report;

Blue Hill Harbor, Section 107 Navigation Improvement Study

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)					TOTAL PROJECT COST (FULLY FUNDED)			
<b>Dispose Dredged Material at Upland Landfill</b>						Program Year (Budget EC): 2021 Effective Price Level Date: 1-Oct- 20 Spent Thru: <b>1-Oct-20</b>								
WBS NUMBER	Civil Works Feature & Sub-Feature Description	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	ESC (%)	COST (\$K)	CNTG (\$K)	REMAINING COST (\$K)	TOTAL FIRST COST (\$K)	ESC (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
<b>12</b>	NAVIGATION PORTS & HARBORS	\$6,402	\$963	15%	\$7,365		\$6,402	\$963	\$7,365	\$7,365	6.0%	\$6,783	\$1,020	\$7,803
			-			-					-			
			-			-					-			
			-			-					-			
<b>CONSTRUCTION ESTIMATE TOTALS:</b>		\$6,402	\$963		\$7,365		\$6,402	\$963	\$7,365	\$7,365	6.0%	\$6,783	\$1,020	\$7,803
01	LANDS AND DAMAGES	\$9			\$9		\$9		\$9	\$9	6.0%	\$10		\$10
30	PLANNING, ENGINEERING & DESIGN	\$304	\$41	14%	\$345		\$304	\$41	\$345	\$345	5.4%	\$320	\$44	\$364
31	CONSTRUCTION MANAGEMENT	\$177	\$30	17%	\$207		\$177	\$30	\$207	\$207	7.9%	\$191	\$32	\$223
<b>PROJECT COST TOTALS:</b>		\$6,892	\$1,034	15%	\$7,926		\$6,892	\$1,034	\$7,926	\$7,926	6.0%	\$7,304	\$1,096	\$8,400

D-12

_____	CHIEF, COST ENGINEERING, Jeffrey Gaeta
_____	PROJECT MANAGER, Mark Habel
_____	CHIEF, REAL ESTATE, Timothy Shugert
_____	CHIEF, PLANNING, John Kennelly
_____	CHIEF, ENGINEERING, Dave Margolis
_____	CHIEF, OPERATIONS, Eric Pedersen
_____	CHIEF, CONSTRUCTION, Sean Dolan
_____	CHIEF, CONTRACTING, Sheila Winston-Vincuilla
_____	CHIEF, PM-PB, Janet Harrington
_____	CHIEF, DPM, Scott Accone

**ESTIMATED TOTAL PROJECT COST: \$8,400**

ESTIMATED FEDERAL COST: **90%** \$7,560

ESTIMATED NON-FEDERAL COST: **10%** \$840

ADDITIONAL 10% NON-FEDERAL COST: \$840

**22 - FEASIBILITY STUDY (CAP studies): \$352**

ESTIMATED FEDERAL COST: 64% **\$226**

ESTIMATED NON-FEDERAL COST: 36% **\$126**

**ESTIMATED FEDERAL COST OF PROJECT \$7,786**

ESTIMATED NON-FEDERAL COST OF PROJECT \$1,806



\*\*\*\* TOTAL PROJECT COST SUMMARY \*\*\*\*

Printed:6/3/2021  
Page 4 of 4

\*\*\*\* CONTRACT COST SUMMARY \*\*\*\*

PROJECT: Blue Hill Section 107  
LOCATION: Blue Hill, Maine  
This Estimate reflects the scope and schedule in report; Blue Hill Harbor, Section 107 Navigation Improvement Study

DISTRICT: New England District  
POC: CHIEF, COST ENGINEERING, Jeffrey Gaeta

PREPARED: 5/19/2021

WBS Structure		ESTIMATED COST				PROJECT FIRST COST Dollar Basis) (Constant				TOTAL PROJECT COST (FULLY FUNDED)				
Dispose Dredged Material at Upland Landfill		Estimate Prepared:		3-Nov-20		Program Year (Budget EC):		2021						
		Estimate Price Level:		1-Oct-20		Effective Price Level Date:		1 -Oct-20						
		RISK BASED												
WBS NUMBER A	Civil Works Feature & Sub-Feature Description B	COST (\$K) C	CNTG (\$K) D	CNTG (%) E	TOTAL (\$K) F	ESC (%) G	COST (\$K) H	CNTG (\$K) I	TOTAL (\$K) J	Mid-Point Date P	ESC (%) L	COST (\$K) M	CNTG (\$K) N	FULL (\$K) O
PHASE 1 or CONTRACT 1														
12	NAVIGATION PORTS & HARBORS	\$6,402	\$963	15.0%	\$7,365		\$6,402	\$963	\$7,365	2023Q1	6.0%	\$6,783	\$1,020	\$7,803

D-13

### Abbreviated Risk Analysis

Project (less than \$40M): **Blue Hill Harbor Section 107 Navigation Improvement Study**  
 Project Development Stage/Alternative: **Feasibility (Recommended Plan)**  
 Risk Category: **Low Risk: Typical Construction, Simple**

Alternative: **Tentatively Selected Plan**

Meeting Date: **11/3/2020**

Total Estimated Construction Contract Cost = \$ **2,084,576**

	CWWBS	Feature of Work	Estimated Cost	% Contingency	\$ Contingency	Total
	01 LANDS AND DAMAGES	Real Estate	\$ 9,000	0%	\$ -	\$ 9,000
1	12 02 HARBORS	Mobilization & Demobilization	\$ 362,733	14%	\$ 50,039	\$ 412,772
2	12 02 HARBORS	Dredge Channel & Dispose in EPDS	\$ 1,097,721	17%	\$ 183,082	\$ 1,280,803
3	12 02 HARBORS	Dredge Contam Matl & Place in CAD Cell	\$ 520,276	15%	\$ 80,346	\$ 600,622
4				0%	\$ -	\$ -
5				0%	\$ -	\$ -
6				0%	\$ -	\$ -
7				0%	\$ -	\$ -
8				0%	\$ -	\$ -
9				0%	\$ -	\$ -
10				0%	\$ -	\$ -
11				0%	\$ -	\$ -
12	All Other	Remaining Construction Items	\$ 103,846	5.2%	\$ -	\$ 103,846
13	30 PLANNING, ENGINEERING, AND DESIGN	Planning, Engineering, & Design	\$ 304,000	14%	\$ 41,412	\$ 345,412
14	31 CONSTRUCTION MANAGEMENT	Construction Management	\$ 177,000	17%	\$ 29,793	\$ 206,793
XX	FIXED DOLLAR RISK ADD (EQUALLY DISPERSED TO ALL, MUST INCLUDE JUSTIFICATION SEE BELOW)				\$ -	

Totals					
	Real Estate	\$ 9,000	0%	\$ -	\$ 9,000.00
	Total Construction Estimate	\$ 2,084,576	15.04%	\$ 313,467	\$ 2,398,043
	Total Planning, Engineering & Design	\$ 304,000	13.62%	\$ 41,412	\$ 345,412
	Total Construction Management	\$ 177,000	16.83%	\$ 29,793	\$ 206,793
	Total Excluding Real Estate	\$ 2,565,576	14.99%	\$ 384,672	\$ 2,950,248
		Base 50% 80%			
Confidence Level Range Estimate (\$000's)		\$2,566k	\$2,796k	\$2,950k	

\* 50% based on base is at 5% CL.

**Fixed Dollar Risk Add:** (Allows for additional risk to be added to the risk analysis. Must include justification. Does not allocate to Real Estate.

## Blue Hill Harbor Section 107 Navigation Improvement Study

Feasibility (Recommended Plan)

Abbreviated Risk Analysis

Meeting Date: 3-Nov-20

Risk Level					
Very Likely Likely Possible Unlikely	2	3	4	5	5
	1	2	3	4	5
	0	1	2	3	4
	0	0	1	2	3
	Negligible	Marginal	Moderate	Significant	Critical

## Risk Register

Risk Element	Feature of Work	Concerns	PDT Discussions & Conclusions (Include logic & justification for choice of Likelihood & Impact)	Impact	Likelihood	Risk Level
<b>Project Management &amp; Scope Growth</b>						<b>Maximum Project Growth 40%</b>
PS-1	Mobilization & Demobilization	n/a		Negligible	Unlikely	0
PS-2	Dredge Channel & Dispose in EPDS	There is a concern that the customer, Town of Blue Hill, may request a design change to the size of the turning basin.	To date, there have been no requests to alter the existing design or to add new design components. As such, the PDT is confident that there is negligible risk associated with this concern.	Negligible	Unlikely	0
PS-3	Dredge Contam Matl & Place in CAD Cell	There is a concern that the customer, Town of Blue Hill, may request a design change to the size of the turning basin.	To date, there have been no requests to alter the existing design or to add new design components. As such, the PDT is confident that there is negligible risk associated with this concern.	Negligible	Unlikely	0
PS-13	Planning, Engineering, & Design	There is a concern that the customer, Town of Blue Hill, may request a design change to the size of the turning basin.	To date, there have been no requests to alter the existing design or to add new design components. As such, the PDT is confident that there is negligible risk associated with this concern.	Negligible	Unlikely	0
PS-14	Construction Management	n/a		Negligible	Unlikely	0
<b>Acquisition Strategy</b>						<b>Maximum Project Growth 30%</b>
AS-1	Mobilization & Demobilization	It's possible that this project will be awarded using the 8(a) or small business set aside. Setting the project aside will limit the number of contractors available to dredge (dredging is already a fairly limited market on the East Coast; dredging in Maine is an even smaller pool of contractors. A small contractor may have difficulty securing the proper equipment necessary to complete the job, thereby impeding their ability to mobilize to the site.	Professional experience indicates that, even if we were to set this project aside, USACE would likely include a DRC in the contract which requires the KTR to demonstrate they have the correct equipment and have performed similar work in the past. This DRC has been successful in the past for weeding out unqualified KTRs.	Moderate	Unlikely	1
AS-2	Dredge Channel & Dispose in EPDS	It's possible that this project will be awarded using the 8(a) or small business set aside. Setting the project aside will limit the number of contractors available to dredge (dredging is already a fairly limited market on the East Coast; dredging in Maine is an even smaller pool of contractors. A small contractor may have difficulty securing the proper equipment necessary to complete the dredging of non-contaminated material and disposing in the Eastern Passage Disposal Site.	Professional experience indicates that, even if we were to set this project aside, USACE would likely include a DRC in the contract which requires the KTR to demonstrate they have the correct equipment and have performed similar work in the past. This DRC has been successful in the past for weeding out unqualified KTRs.	Marginal	Unlikely	0
AS-3	Dredge Contam Matl & Place in CAD Cell	It's possible that this project will be awarded using the 8(a) or small business set aside. Setting the project aside will limit the number of contractors available to dredge (dredging is already a fairly limited market on the East Coast; dredging in Maine is an even smaller pool of contractors. A small contractor may not have experience constructing CAD cells.	CAD construction is a fairly straight-forward task (essentially, it's just a large hole in the ground). As such, the PDT is not concerned with a lack of experience on the part of the winning KTR. Professional experience indicates that if the KTR can dredge a channel, they can build a CAD cell.	Marginal	Unlikely	0
AS-13	Planning, Engineering, & Design	n/a		Negligible	Unlikely	0

AS-14	Construction Management	It's possible that this project will be awarded using the 8(a) or small business set aside. Setting the project aside will limit the number of contractors available to dredge (dredging is already a fairly limited market on the East Coast; dredging in Maine is an even smaller pool of contractors. A small contractor may not be familiar with USACE pre-construction submittal requirements, leading to complications in effective construction management.	Professional/historical experience indicates that many of NAE's dredging projects in Maine have been awarded to competent small businesses. It's a fair assumption that these same businesses would win the contract for this work and thus, NAE would have a KTR onsite who is familiar with USACE processes.	Moderate	Unlikely	1
<b>Construction Elements</b>				<b>Maximum Project Growth</b>		<b>15%</b>
CE-1	Mobilization & Demobilization	n/a		Negligible	Unlikely	0
CE-2	Dredge Channel & Dispose in EPDS	The KTR may encounter ledge/bedrock during dredging operations. Such an encounter would either require the KTR to conduct underwater blasting operations (along with rock removal) or USACE to alter the layout of the channel/anchorage. Both alternatives would represent a delay to the contract and a significant construction contract modification for differing site conditions.	The PDT performed a thorough set of geotechnical investigations in the areas where the channel is to be built, which indicate that the material is primarily sand. In the unlikely case that ledge is encountered, it's possible that the channel or anchorage could be relocated to circumvent blasting.	Significant	Unlikely	2
CE-3	Dredge Contam Matl & Place in CAD Cell	The KTR may encounter ledge/bedrock during dredging operations. Such an encounter would either require the KTR to conduct underwater blasting operations (along with rock removal) or USACE to alter the layout of the channel/anchorage. Both alternatives would represent a delay to the contract and a significant construction contract modification for differing site conditions.	The PDT performed a thorough set of geotechnical investigations in the area where the CAD cell is to be built, which indicate the material is primarily sand. If ledge was encountered, the CAD cell could easily be resized to accommodate the required dredge volume.	Moderate	Unlikely	1
CE-13	Planning, Engineering, & Design	The KTR may encounter ledge/bedrock during dredging operations. Such an encounter would either require the KTR to conduct underwater blasting operations (along with rock removal) or USACE to alter the layout of the channel/anchorage. Both alternatives would represent a delay to the contract and a significant construction contract modification for differing site conditions.	The PDT performed a thorough geotechnical investigation in the project areas, which indicate that the material is primarily sand. In the unlikely case that ledge is encountered, the design team is confident that a change could be completed quickly, such as CAD resizing or channel/anchorage relocation.	Moderate	Unlikely	1
D-16 CE-14	Construction Management	The KTR may encounter ledge/bedrock during dredging operations. Such an encounter would either require the KTR to conduct underwater blasting operations (along with rock removal) or USACE to alter the layout of the channel/anchorage. Both alternatives would represent a delay to the contract and a significant construction contract modification for differing site conditions.	The PDT performed a thorough geotechnical investigation in the project areas, which indicate that the material is primarily sand. If ledge was encountered, a construction contract mod would need to be processed; however, the team is confident that the geotech investigation has reduced this risk sufficiently.	Significant	Unlikely	2
<b>Specialty Construction or Fabrication</b>				<b>Maximum Project Growth</b>		<b>50%</b>
SC-1	Mobilization & Demobilization	n/a		Negligible	Unlikely	0
SC-2	Dredge Channel & Dispose in EPDS	The PDT does not have concerns regarding any "special" aspects of this feature of work.	Dredging is a rather straight-forward task and NAE has had great historical success designing, awarding, and managing these types of contracts.	Negligible	Unlikely	0
SC-3	Dredge Contam Matl & Place in CAD Cell	The KTR may not have an environment bucket on hand with which to dredge contaminated materials in the top 2-ft of the project.	The PDT intends to the use a DRC to screen out unqualified bidders. As part of the DRC, bidders will be required to submit an equipment list to demonstrate their qualifications.	Negligible	Unlikely	0
SC-13	Planning, Engineering, & Design	The PDT does not have concerns regarding any "special" aspects of this feature of work.	Dredging is a rather straight-forward task and NAE has had great historical success designing, awarding, and managing these types of contracts.	Negligible	Unlikely	0
SC-14	Construction Management	The PDT does not have concerns regarding any "special" aspects of this feature of work.	Dredging is a rather straight-forward task and NAE has had great historical success designing, awarding, and managing these types of contracts.	Negligible	Unlikely	0
<b>Technical Design &amp; Quantities</b>				<b>Maximum Project Growth</b>		<b>20%</b>
T-1	Mobilization & Demobilization	n/a		Negligible	Unlikely	0

T-2	Dredge Channel & Dispose in EPDS	The design is based on a 2012 dredge survey and there is a concern that a significant amount of deposition from the tributary rivers will increase the quantity of material to be dredged between the feasibility study and contract award.	USACE has already completed multiple surveys within the harbor, which demonstrate that the rate of deposition is very low to negligible. As such, the PDT has confidence that the quantities developed during this study will be representative of field conditions at time of award.	Marginal	Unlikely	0
T-3	Dredge Contam Matl & Place in CAD Cell	The design is based on a 2012 dredge survey and there is a concern that a significant amount of deposition from the tributary rivers will increase the quantity of material to be dredged between the feasibility study and contract award.	USACE has already completed multiple surveys within the harbor, which demonstrate that the rate of deposition is very low to negligible. As such, the PDT has confidence that the quantities developed during this study will be representative of field conditions at time of award. Even if this were not the case, the USACE has authorization to dig a deeper CAD, if needed, to accommodate additional contaminated material.	Negligible	Unlikely	0
T-13	Planning, Engineering, & Design	The design is based on a 2012 dredge survey and there is a concern that a significant amount of deposition from the tributary rivers will increase the quantity of material to be dredged between the feasibility study and contract award.	USACE has already completed multiple surveys within the harbor, which demonstrate that the rate of deposition is very low to negligible. As such, the PDT has confidence that the quantities developed during this study will be representative of field conditions at time of award. Even if this were not the case, the impact to the Design of the contract would be negligible.	Negligible	Unlikely	0
T-14	Construction Management	n/a		Negligible	Unlikely	0
<b>Cost Estimate Assumptions</b>				<b>Maximum Project Growth</b>		<b>25%</b>
EST-1	Mobilization & Demobilization	The Mobilization & Demobilization distances used in the CEDEP file may not be sufficient to capture the winning contractor's costs for this feature of work.	The PDT is confident, based on similar dredging jobs in Maine, that a Maine-based contractor will win the work. The estimate has assumed a New York-based contractor, so it's unlikely that these costs are insufficient.	Marginal	Unlikely	0
EST-2	Dredge Channel & Dispose in EPDS	The cost estimate might not carry an adequate set of assumptions in the CEDEP file to capture the project's constraints.	The assumptions contained within the CEDEP files have been reviewed by the PDT members; no significant disagreements or concern were raised by the PDT at that time. Further reviews to be conducted in-house will be completed by both the local district and the CX, reducing the risk that a major oversight on the part of the estimator won't be found prior to PED phase.	Moderate	Unlikely	1
EST-3	Dredge Contam Matl & Place in CAD Cell	The cost estimate might not carry an adequate set of assumptions in the CEDEP file to capture the project's constraints.	The assumptions contained within the CEDEP files have been reviewed by the PDT members; no significant disagreements or concern were raised by the PDT at that time. Further reviews to be conducted in-house will be completed by both the local district and the CX, reducing the risk that a major oversight on the part of the estimator won't be found prior to PED phase.	Moderate	Unlikely	1
EST-13	Planning, Engineering, & Design	The PED phase has been estimated at \$182,000; there is a concern that this number is too low because it is not based on a detailed fee estimate created by individual team members.	The FS report is to be reviewed in-house by experienced section chiefs, so, while it is possible that the budget is too low, the impacts are mitigated by this layer of review.	Marginal	Possible	1
EST-14	Construction Management	The Construction Management feature of work has been estimated at \$110,000; there is a concern that this number is too low because it is not based on a detailed fee estimate created by individual team members.	The FS report is to be reviewed in-house by experienced section chiefs, so, while it is possible that the budget is too low, the impacts are mitigated by this layer of review.	Marginal	Possible	1
<b>External Project Risks</b>				<b>Maximum Project Growth</b>		<b>20%</b>
EX-1	Mobilization & Demobilization	It's possible that the contractor will encounter significant weather-related delays that will impede his ability to mobilize to the site. The project is in Maine, meaning there is potential for ice dams in the channel which may obstruct contractor access.	The PDT finds there to be a credible risk of cost growth related to harsh winter conditions. However, the team intends to mitigate these risks by requiring bidders to demonstrate their ability to achieve a suitable dredging production rate via the DRC.	Marginal	Possible	1

EX-2	Dredge Channel & Dispose in EPDS	It's possible that the contractor will encounter significant weather-related delays that will impede his dredging productivity. The project is in Maine, meaning there is potential for ice dams in the channel which may obstruct contractor access.	The PDT finds there to be a credible risk of cost growth related to harsh winter conditions. However, the team intends to mitigate these risks by requiring bidders to demonstrate their ability to achieve a suitable dredging production rate via the DRC.	Marginal	Possible	1
EX-3	Dredge Contam Matl & Place in CAD Cell	It's possible that the contractor will encounter significant weather-related delays that will impede his dredging productivity. The project is in Maine, meaning there is potential for ice dams in the channel which may obstruct contractor access.	The PDT finds there to be a credible risk of cost growth related to harsh winter conditions. However, the team intends to mitigate these risks by requiring bidders to demonstrate their ability to achieve a suitable dredging production rate via the DRC.	Marginal	Possible	1
EX-13	Planning, Engineering, & Design	n/a		Negligible	Unlikely	0
EX-14	Construction Management	n/a		Negligible	Unlikely	0

COE Standard Report Selections

Title Page

This estimate captures costs for the preferred alternative for dredging Blue Hill Harbor down to 6-ft below existing depth. The top 2-ft of the harbor sediments are contaminated with petroleum-based products in the tidal reaches and are to be disposed of in the CAD cell. Alternative assumes that all clean materials will be disposed of in the Eastern Passage Disposal Site (EPDS). CEDEP was used in conjunction with MII to develop this alternative. All work is assumed to be self-performed by the prime contractor.

□□

Escalation for non-CEDEP items taken from Q1FY16 to Q1FY21 for "Navigation Ports & Harbors". No escalation applied to CEDEP items as they are priced using Q1FY21 pricing. Note that the escalation applied in MII is intended to bring all costs to Q1FY21; the remaining escalation is applied in the TPCS report. Contingency set at 0% because it will be applied in TPCS report.

D-19

Estimated by J Masey

Designed by L. Jacobs

Prepared by Jeremiah Masey

Preparation Date 5/19/2021

Effective Date of Pricing 10/1/2020

Estimated Construction Time 90 Days

This report is not copyrighted, but the information contained herein is For Official Use Only.

Description	Quantity	UOM	DirectCost	SubCMU	PrimeCMU	Escalation	Contingency	ProjectCost
<b>1.1 Recommended Plan: 6-ft Channel &amp; CAD Cell</b>	<b>72,950</b>	<b>CY</b>	<b>1,579,382</b>	<b>0</b>	<b>505,194</b>	<b>0</b>	<b>0</b>	<b>2,084,576</b>
<b>1.1.1 General Requirements</b>	<b>2</b>	<b>MO</b>	<b>78,679</b>	<b>0</b>	<b>25,167</b>	<b>0</b>	<b>0</b>	<b>103,846</b>
<b>1.1.2 Mobilization / Demobilization</b>	<b>1</b>	<b>EA</b>	<b>274,825</b>	<b>0</b>	<b>87,908</b>	<b>0</b>	<b>0</b>	<b>362,733</b>
<b>1.1.3 Mechanical Dredging</b>	<b>71,470</b>	<b>CY</b>	<b>1,225,878</b>	<b>0</b>	<b>392,119</b>	<b>0</b>	<b>0</b>	<b>1,617,997</b>
<b>1.1.3.1 Dredge Channel &amp; Dispose in EPDS</b>	<b>52,100</b>	<b>CY</b>	<b>617,385</b>	<b>0</b>	<b>197,482</b>	<b>0</b>	<b>0</b>	<b>814,867</b>
<b>1.1.3.2 Dredge CAD Cell</b>	<b>19,500</b>	<b>CY</b>	<b>214,305</b>	<b>0</b>	<b>68,549</b>	<b>0</b>	<b>0</b>	<b>282,854</b>
<b>1.1.3.3 Fill CAD Cell w/ Contaminated Material</b>	<b>10,600</b>	<b>CY</b>	<b>326,692</b>	<b>0</b>	<b>104,498</b>	<b>0</b>	<b>0</b>	<b>431,190</b>
<b>1.1.3.4 Cap CAD Cell</b>	<b>8,800</b>	<b>CY</b>	<b>67,496</b>	<b>0</b>	<b>21,590</b>	<b>0</b>	<b>0</b>	<b>89,086</b>
<b>1.2 Alternative: 6-ft Channel &amp; Upland Disposal</b>	<b>71,470</b>	<b>CY</b>	<b>4,850,361</b>	<b>0</b>	<b>1,551,475</b>	<b>0</b>	<b>0</b>	<b>6,401,836</b>
<b>1.2.1 General Requirements</b>	<b>4</b>	<b>MO</b>	<b>136,663</b>	<b>0</b>	<b>43,714</b>	<b>0</b>	<b>0</b>	<b>180,378</b>
<b>1.2.2 Marine Mob/Demob</b>	<b>1</b>	<b>EA</b>	<b>274,825</b>	<b>0</b>	<b>87,908</b>	<b>0</b>	<b>0</b>	<b>362,733</b>
<b>1.2.3 Overland Mob/Demob</b>	<b>1</b>	<b>EA</b>	<b>12,456</b>	<b>0</b>	<b>3,984</b>	<b>0</b>	<b>0</b>	<b>16,440</b>
<b>1.2.4 Dredging</b>	<b>71,471</b>	<b>CY</b>	<b>1,214,791</b>	<b>0</b>	<b>388,573</b>	<b>0</b>	<b>0</b>	<b>1,603,363</b>
<b>1.2.5 Overland Work</b>	<b>10,591</b>	<b>CY</b>	<b>3,211,626</b>	<b>0</b>	<b>1,027,296</b>	<b>0</b>	<b>0</b>	<b>4,238,923</b>
<b>1.2.5.1 Loading &amp; Hauling to Offsite Treatment Plant</b>	<b>1</b>	<b>EA</b>	<b>2,424,489</b>	<b>0</b>	<b>775,516</b>	<b>0</b>	<b>0</b>	<b>3,200,006</b>
<b>1.2.5.2 Mat'l Dewatering &amp; Processing</b>	<b>1</b>	<b>EA</b>	<b>787,137</b>	<b>0</b>	<b>251,780</b>	<b>0</b>	<b>0</b>	<b>1,038,917</b>
<b>1.2.5.2.1 Temp Power to Run Equipment</b>	<b>1</b>	<b>EA</b>	<b>4,263</b>	<b>0</b>	<b>1,364</b>	<b>0</b>	<b>0</b>	<b>5,626</b>